


MUSTANG

GUARDRAIL TO BE 36" HIGH (MIN.) AND SHALL HAVE INTERMEDIATE RAILS SUCH THAT A SPHERE 4" IN DIAMETER CANNOT PASS THROUGH. HANDRAILS ARE REQUIRED ON ALL STAIRWAYS WITH 2 OR MORE RISERS.

PROVIDE CAULKING AND MINIMUM 9" COUNTER FLASHING AT ALL EXTERIOR DOORS/WINDOWS PER MANUFACTURER INSTALLATION REQUIREMENTS.


- MASONRY NOTE:**
- 1. MASONRY VENEER SHALL HAVE CORROSION RESISTANT ANCHOR TIES OF NOT LESS THAN 22 GA. x 7/8" SPACED NOT MORE THAN 24" O.C. HORIZONTAL AND SUPPORT A MAXIMUM OF 2 SQUARE FEET OF WALL AREA. AROUND WALL OPENINGS GREATER THAN 16" ADDITIONAL TIES ARE REQUIRED TO BE SPACED A MAXIMUM OF 36" O.C. AND BE WITHIN 12" OF THE OPENING. PROVIDE 26 GAUGE FLASHING FROM FOUNDATION UP FIRST 3 COURSES. CULTURED STONE TO BE INSTALLED PER MANUFACTURERS SPECIFICATIONS.
 - 2. FOR BRICK SUPPORT OVER OPENINGS, SEE VENEER LINTEL TABLE ON SHEET S1
 - 3. KEEPHOLES SHALL BE PROVIDED IN THE OUTSIDE RYTHE OF MASONRY WALLS @ 24" O.C. AND BE NO LESS THAN 3/16" LOCATED IMMEDIATELY ABOVE FLASHING. FLASHING TO BE 26 GAUGE FROM FOUNDATION UP FIRST THREE COURSES.



FRONT ELEVATION
SCALE: 1/4"=1'-0"

* SHEETROCK FASTENER SPACING
TO BE 1' o.c. TO ALL STUDS, TOP
AND BOTTOM PLATES ON THESE
WALLS

GUARDRAIL TO BE 36" HIGH (MIN.)
AND SHALL HAVE INTERMEDIATE
RAILS SUCH THAT A SPHERE 4" IN
DIAMETER CANNOT PASS THROUGH.
HANDRAILS ARE REQUIRED ON ALL
STAIRWAYS WITH 2 OR MORE RISERS.



MAIN FLOOR PLAN
SCALE: 1/4"=1'-0"
1064 S.F.


Hearthstone Home Design
© Copyright 2018 Hearthstone Design, Inc. All Rights Reserved.
Tel: 1-866-298-2505
www.hearthstonedesign.com

GLEAMWATER HOTES
WILD HORSE RANCHES
LOT #104 - STANSBURY PARK
DATE: 14 MAY 2018

PLAN TS-2305b-029

N SHEET

** EXTEND SHEATHING TO
BOTTOM OF JOISTS



GUARDRAIL TO BE 36" HIGH (MIN)
AND SHALL HAVE INTERMEDIATE
RAILS SUCH THAT A SPHERE 4" IN
DIAMETER CANNOT PASS THROUGH.
HANDRAILS ARE REQUIRED ON ALL
STAIRWAYS WITH 2 OR MORE RISERS.

UPPER FLOOR PLAN
SCALE: 1/4"=1'-0" 1236 S.F.



PRELIMINARY
THIS DRAWING IS THE PROPERTY OF HEARTSTONE HOME DESIGN, INC. AND IS TO BE USED ONLY FOR THE PROJECT AND SITE SPECIFICALLY NOTED THEREON. ANY REUSE OR MODIFICATION OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION OF HEARTSTONE HOME DESIGN, INC. IS STRICTLY PROHIBITED.

Heartstone Home Design
© Copyright 2018 Heartstone Design, Inc. All Rights Reserved.
Tel: 1-866-298-2505
www.heartstonedesign.com

GLEAMATER HOTES
WILD HORSE RANCHES
LOT #104 - STANSBURY PARK
DATE: 14 MAY 2018

PLAN TS-2305b-029

SHEET
3